



APPROVED FOR PRODUCTION:	APPROVED FOR PRODUCTION W/ CHANGES :	RESUBMITTAL REQUIRED:
--------------------------	--------------------------------------	-----------------------

**SPECIFICATIONS:**

**CONCRETE:** Class 1 concrete with design strength of 4500 PSI at 28 days. Unit is of monolithic construction at floor and first stage of wall.

**REINFORCEMENT:** Grade 60 reinforced with steel rebar conforming to ASTM A-615 on required centers.

**C.I. CASTINGS:** Cast Iron Ring & Cover shall be nominal 24" and traffic duty

**ENGINEERING DATA:**

Grease Trap is structurally and hydraulically engineered conforming to Louisiana Department of Health & Hospitals Plumbing Code. Nominal liquid capacity as indicated on plan.

Field excavation and preparation shall be completed prior to delivery of grease trap. Use dimensional data as shown.

**300 GALLON GREASE TRAP**

MODEL # **GCP-300GT (NON-TR)**

SCALE: NOT TO SCALE	DATE: 5/21/11	DRAWN: CG	CHECKED: CG
---------------------	---------------	-----------	-------------

28021 Coker-Vail Road Phone (225) 567 - 2700	Holden, LA 70744 Fax (225) 567 - 3089
---	--

www.gaineyconcrete.com

