



APPROVED FOR PRODUCTION:

APPROVED FOR PRODUCTION W/ CHANGES :

RESUBMITAL REQUIRED:

SPECIFICATIONS:

CONCRETE: Class 1 concrete with design strength of 4500 PSI at 28 days. Unit is of monolithic construction at floor and first stage of wall. Baffle is slide in type.

REINFORCEMENT: Grade 60 reinforced with steel rebar conforming to ASTM A-615 on required centers.

C.I. CASTINGS: Cast Iron Ring & Cover shall be nominal 24" and traffic duty

ENGINEERING DATA:

Capacity Holding: 106 cubic ft, 792 gallons

Field excavation and preparation shall be completed prior to delivery of sand separator. Use dimensional data as shown.

750 GALLON SAND SEPARATOR

GCP-750SS (NON-TR)

SCALE: NOT TO SCALE DATE: 06/04/14 DRAWN: AG CHECKED:

28021 Coker-Vail Road
Phone (225) 567 - 2700

Holden, LA 70744
Fax (225) 567 - 3089

www.gaineyconcrete.com

