



APPROVED FOR PRODUCTION:

APPROVED FOR PRODUCTION W/ CHANGES :

RESUBMITTAL REQUIRED:

SPECIFICATIONS:

CONCRETE: Class 1 concrete with design strength of 4500 PSI at 28 days. Unit is of monolithic construction at floor and first stage of wall. Baffle is slide in type.

REINFORCEMENT: Grade 60 reinforced with steel rebar conforming to ASTM A-615 on required centers.

C.I. CASTINGS: Cast Iron Ring & Cover shall be nominal 24" and traffic duty

ENGINEERING DATA:

Nominal liquid capacity as indicated on plan. Field excavation and preparation shall be completed prior to delivery of oil and water separator. Use dimensional data as shown.

**1000 GALLON
OIL & WATER SEPARATOR**

MODEL # **GCP-1000OWS**



SCALE: NOT TO SCALE DATE: 5/21/11 DRAWN: CG CHECKED: CG
28021 Coker-Vail Road Holden, LA 70744
Phone (225) 567 - 2700 Fax (225) 567 - 3089
www.gaineysconcrete.com