



APPROVED FOR PRODUCTION:	APPROVED FOR PRODUCTION W/ CHANGES :	RESUBMITTAL REQUIRED:
--------------------------	--------------------------------------	-----------------------

SPECIFICATIONS:

CONCRETE: Class 1 concrete with design strength of 4500 PSI at 28 days. Unit is of monolithic construction at floor and first stage of wall. Baffle is slide in type.

REINFORCEMENT: Grade 60 reinforced with steel rebar conforming to ASTM A-615 on required centers.

C.I. CASTINGS: Cast Iron Ring & Cover shall be nominal 24" and traffic duty

ENGINEERING DATA:

Nominal liquid capacity as indicated on plan. Field excavation and preparation shall be completed prior to delivery of oil and water separator. Use dimensional data as shown.

**1500 GALLON
OIL & WATER SEPARATOR**

MODEL # **GCP-1500OWS(TR)**

SCALE: NOT TO SCALE	DATE: 5/21/11	DRAWN:CG	CHECKED:CG
---------------------	---------------	----------	------------

28021 Coker-Vail Road Phone (225) 567 - 2700	Holden, LA 70744 Fax (225) 567 - 3089
---	--

www.gaineyconcrete.com

