



APPROVED FOR PRODUCTION:

APPROVED FOR PRODUCTION W/ CHANGES :

RESUBMITTAL REQUIRED:

**SPECIFICATIONS:**

**CONCRETE:** Class 1 concrete with design strength of 4500 PSI at 28 days. Unit is of monolithic construction at floor and first stage of wall. Baffle is slide-in type.

**REINFORCEMENT:** Grade 60 reinforced with steel rebar conforming to ASTM A-615 on required centers.

**C.I. CASTINGS:** Cast Iron Ring & Cover shall be nominal 24" and traffic duty

**ENGINEERING DATA:**

Nominal liquid capacity as indicated on plan. Field excavation and preparation shall be completed prior to delivery of oil & water separator. Use dimensional data as shown.

**300 GALLON  
OIL & WATER SEPARATOR**

MODEL # **GCP-300OWS**

SCALE: NOT TO SCALE DATE: 5/21/11 DRAWN: CG CHECKED: CG

28021 Coker-Vail Road  
Phone (225) 567 - 2700

Holden, LA 70744  
Fax (225) 567 - 3089

www.gaineyconcrete.com

